MATERIAL NOTES


- "MAIN SIZE" x 4" TAPPING SLEEVE PER STD. DWG. No. W-12
-) 4" RESILIENT WEDGE GATE VALVE (FLG x FLG) MUELLER A-2360-6 (SEE NOTE 3)
- 3) 4" STD. STEEL SPOOL, WELDED (FLG x FLG) LENGTH VARIES, FIELD VERIFY
- 4 4" STD. STEEL COAL TAR ENAMEL (BITUMASTIC) COATED SPOOL, WELDED (FLG x FLG) 24-INCHES LONG
- 5 3" HERSEY STRAINER, BRONZE (FLG x FLG) W/ BRASS BOLTS
- 3" HERSEY RADIO READ TURBO METER, BRONZE (FLG x FLG) W/ BRASS BOLTS
-) 4" STD. STEEL x 2" SADDLE (F.I.P.T.) DOUBLE STRAP, BRONZE, MUELLER OR APPROVED EQUAL
- 00 4" NUTS, BOLTS, AND GASKET SET
- 9 COAL TAR ENAMEL (BITUMASTIC) COATED 3"x4" BELL REDUCER, WELDED FLANGE
- 10) 2" CLOSE NIPPLE, BRASS
- ig(11ig) 4'x6'x4' METER BOX WITH LID, PER PPHCSD SPECIFICATIONS, CENTERED IN BOX

MATERIAL NOTES (CONTINUE)

- 2" UNION, BRONZE (F.I.P.T. x F.I.P.T.)
- 13) 2"90° ELBOW, BRONZE (F.I.P.T. x F.I.P.T.)
- 14) 2" PIPE, BRASS (M.I.P.T. imes M.I.P.T.) 60" LONG, PLACED OUTSIDE OF BOX
- 15) 2" BALL VALVE CURB STOP, BRONZE (F.I.P.T. x F.I.P.T.) W/ PADLOCK WINGS MUELLER B-20200, OR APPROVED EQUAL, WITH IRRIGATION / VALVE CAN WITH LID
- 16) 2" PIPE, BRASS (M.I.P.T. x M.I.P.T.) LENGTH AS REQ'D, PLACED OUTSIDE OF BOX

GENERAL NOTES

- 1. ALL SERVICE LINES SHALL HAVE A MINIMUM DEPTH OF 24"
- 2. PROVIDE (2" MIN. THICKNESS) GRAVEL BASE FOR METER BOX
- 3. PROVIDE STANDARD VALVE CAN ASSEMBLY FOR EACH GATE VALVE PER STD DWG. No.W- 5 (REQUIRED FOR VALVES OUTSIDE OF METER BOX)
- 4. CONTRACTOR TO PROVIDE BACKFLOW DEVICE AT CUSTOMER CONNECTION POINT
- 5. ALL MATERIALS SHALL BE NEW



1. WHEN A DEVELOPER'S CONTRACTOR INSTALLS A NEW WATER MAIN, CONTRACTOR WILL INSTALL ITEMS No. 1, 2, 3, AND 8 (FIELD FABRICATION)

RECOMMENDED BY

REV.

DATE

APPROVED BY

2. WHEN A DEVELOPER'S PROJECT DOES NOT REQUIRE BY PPHCSD STAFF A NEW WATER MAIN, ALL ITEMS WILL BE INSTALLED

evised: April 22, 2020

ВΥ 3" METER SERVICE ASSEMBLY PHELAN PIÑON HILLS COMMUNITY SERVICES DISTRICT

